SHIMOGA DIVISION.

Dated——*April* 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 10th May 1911, for constructing quarters for the Lady Apothecary at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing quarters for the Lady Apothecary" at Shimoga in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Materials such as roofing and flooring tiles supplied by Government should be taken over and used on the work.

10. A progress of at least Rs. 2,500 should be shown before the 15th June next on work and materials.

Dispensary and Lying-in Wards for Females at Sagar.

No.	Items of work	Per	Dispensary and wards	Lady Medical Officer	Quarters for midwife	Dead house	Kitchen	Latrine	Total
			Quantity	Quantity	Quantity	Quantity	Quantity	Quantity	Quantity
1	Clearing site and levelling ground.	L. S.	L. S.	L. S.	L. S.	L. S.	L. S.	L. S.	L. S.
2	Earthwork, excavation ...	C. yds.	147	35	...	16	7	...	205
3	Earthwork, filling	Do	69	...	22	...	...	...	91
4	Burnt brick in chunam, foundation and basement.	C. ft.	4,898	952	623	318	240	...	7,031
5	Burnt brick in chunam, superstructure.	Do	6,897	2,463	1,376	341	352	...	11,429
6	Burnt brick in chunam, arch work.	Do	84	L. S.	...	...	18	...	102
7	Burnt stone slabs dressed and fixed.	S. ft.	538	307	168	44	18	...	1,075
8	Plastering with chunam ...	Sqr.	106·07	49·58	27·64	8·56	7·49	...	199·34
9	White and colour washing ...	Do	106·07	49·58	27·64	8·56	7·49	...	199·34
10	Flooring with Mangalore tiles on 3" concrete bed and cement pointing.	Do	9·54	3·12	2·00	...	...	...	14·66
11	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing.	Do	7·56	3·40	1·42	1·50	·58	...	14·46
12	Teak-wood pannelled doors including frames, iron work and locks, etc.	S. ft.	286	82	...	...	23	...	391
13	Teak-wood windows, inside glazed shutters, out side pannelled shutters and iron bars, etc. complete.	Do	244	53	41	...	...	...	338
14	Teak-wood ventilators including glazed shutters and iron bars, etc.	Do	118	26	21	...	...	...	165
15	Teak-wood work wrought and put up.	Do	188	...	..	28	11	...	227
16	Roofing with 1st class Mangalore tiles, teak reepers, nails, etc.	Sqr.	33·21	13·56	7·36	3·78	2·00	...	59·9
17	Roof with Mangalore ceiling tiles.	Do	11·90	4·04	4·26	...	...	...	20·20

Dispensary and Lying-in Wards for Females at Sagar.—*concld.*

No.	Items of work	Per	Dispensary and wards	Lady Medical Officer	Quarters for midwife	Dead house	Kitchen	Latrine	Total
			Quantity	Quantity	Quantity	Quantity	Quantity	Quantity	Quantity
18	Mangalore ridge tiles ...	R. ft.	136	26	26	...	15	...	203
19	Teak-wood eaveboard ...	Do	382	160	126	79	58	...	805
20	Teak-wood columns including base and capitals.	Each	13	6	3	...	...	...	22
21	Painting to doors and windows	Sqr.	12·96	8·43	3·31	1·00	1·00	...	26·70
22	Wood-oiling to wood work ...	Do	30·00	...	...	1·50	...	...	31·50
23	Tarring to wood work ...	Do	5·00	L. S.	L. S.	2·00	...	...	7·00
24	Zinc sheets to valley ...	Each	6	Do	...	...	...	...	6
25	Teak-wood sun-shades ...	Do	10	...	...	...	...	...	10
26	Teak-wood finials	Do	5	...	...	2	2	...	9
27	Honne wood work with wood-oiling complete.	C. ft.	...	64	39·29	...	...	..	103·29
28	Coping including plastering ...	R. ft.	...	79	49	...	...	...	128
29	Constructing V-shaped drain ...	L. S. Rs.	...	L. S.	L. S.	...	...	...	L. S.
30	Teak-wood battened doors complete.	S. ft.	...	60	103	...	...	...	163
31	Teak-wood battened windows ..	Do	...	42	...	...	7	...	49
32	Constructing combined chimney to bath and kitchen room.	L. S.	...	L. S.	L. S.	...	...	...	L. S.
33	Constructing seats in latrine, stone flagging cement pointing and tarring 3 feet high drainage pipes.	Do	...	Do	Do	...	...	...	Do
34	Pestle and mortar ...	Do	...	Do	Do	...	...	...	Do
35	Sinking well in the compound including parapets and gally, etc., complete.	Do	..	Do	Do	...	...	...	Do
36	Iron hold-fasts to doors and windows.	Each	...	98	46	..	...	...	144
37	Binding wall of brick in chunam.	R. ft.	...	...	45	...	...	...	45
38	Burnt stone slabs for table (6").	S. ft.	...	...	...	44	...	...	44
39	Cupboard	L. S.	...	...	L. S.	...	..	...	L. S.
40	Honey comb tile work ...	Sqr.	...	...	...	1·39	..	...	1·39
41	Ventilating tiles	Each	...	...	...	4	4	...	8
42	Concrete foundation ...	C. ft.	...	...	...	102	...	120	222
43	Teak-wood ordinary doors and windows	S. ft.	...	...	...	48	...	...	48
44	Iron plate for chimney ...	lbs.	...	...	...	...	218	...	218
45	Asphalt flooring ...	Sqr.	...	...	...	..	..	1·60	1·60
46	Gravelling the compound ..	L. S.	...	L. S.	L. S.	...	...	...	L. S.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 10th May 1911, for constructing a Female Dispensary at Sagar, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing Female Dispensary at Sagar," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Materials such as roofing and flooring tiles, if any, supplied by Government should be taken over by the contractor and utilised on the work.

10. A progress of at least Rs. 3,500 should be shown before the 15th June next on work and materials.

Lady Hospital Assistant's Quarters at Shimoga.

Items of work	Per	Lady Hospital Assistant's quarters at Shimoga	Out houses for the above	Total
		Quantity	Quantity	Quantity
Earthwork, excavation	C. yd.	120	29	149
Concrete in lime mortar	C. ft.	1,071	262	1,333
Burnt stone in lime mortar	„	2,637	398	3,035
Burnt brick in lime mortar	„	4,241	704	4,945
Burnt stone slabs 6" thick well dressed and fixed.	S. ft.	614	53	667
Pointing with lime mortar	Sqr.	3·41	·80	4·21
Plastering with do ...	„	66·27	13·84	80·11
Flooring with Cuddapah slabs on 3" concrete bed and cement pointing.	„	3·64	·54	4·18
Flooring with 1st class Mangalore tiles on 3" concrete bed and cement pointing.	„	7·25	1·28	8·53
Armoured concrete work	C. ft.	24	...	24
Tying with wire	No.	63	...	63
Iron rods for armouring ...	lb.	1,638	...	1,638
Roofing with 1st class Mangalore tiles including teak reepers.	Sqr.	23·29	4·56	27·85
Mangalore ridge tiles set in mortar ...	R. ft.	96	29	125
Mangalore ventilating tiles	No.	8	8	16
Teak-wood pannelled doors including frames and iron-work, etc., complete.	S. ft.	277	36	313
Teak-wood windows, pannelled outside and glazed shutters inside, including iron bars, etc.	„	63	...	63
Teak-wood ventilators, glazed shutters with iron bars, etc.	„	118	18	136
Teak-wood work wrought and put up, including oiling, etc.	C. ft.	125·06	18·41	143·47
Teak-wood eaveboard, ornamental ...	R. ft.	264	87	351
Fish plates for connecting the valley rafters, etc.	L. S.	L. S.	...	L. S.
Zinc gutter to valleys	R. ft.	96	...	96
Sun shades as per plan with painting ...	Each	4	...	4
Whitewashing and colour washing ...	Sqr.	66·27	13·84	80·11
Painting to doors and windows	„	7·98	1·26	9·24
Teak-wood planking for wall almirahs (1" plank).	S. ft.	32	...	32
Earthwork, filling the basement	C. yd.	71	...	71
Masonry finials	Each	5	...	5
Masonry binding walls over tiles ...	R. ft.	84	24	108
Teak-wood pannelled windows with iron bars, etc; complete.	S. ft.	...	9	9
Honeycomb tile work	Sqr.	...	·22	·22
Wood-oiling	L. S.	....	L. S.	L. S.
Constructing kitchen flue	L. S.	...	L. S.	L. S.

F. A. STEELE,
Executive Engineer.